



॥ सा विद्या या विमुक्तये ॥

स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड

“ज्ञानतीर्थ” परिसर, विष्णुपुरी, नांदेड - ४३१६०६ (महाराष्ट्र)

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY NANDED

“Dnyanteerth”, Vishnupuri, Nanded - 431606 Maharashtra State (INDIA)

Established on 17th September 1994 – Recognized by the UGC U/s 2(f) and 12(B), NAAC Re-accredited with 'A' Grade

ENGINEERING SECTION

Phone: (02462) 229562

website: srtmun.ac.in

e-mail: eesrtmun@gmail.com

संदर्भ : काअका/२०१८-१९/६४३

दिनांक : ०७/०२/२०१९

निविदा सूचना

कुलसचिव, स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड हे खालील कामाचे सिलंबद निविदा मागवित आहेत.

अ.क्र.	कामाचे नांव	कामाची अंदाजित किंमत	इसारा रक्कम	को-या निविदेची किंमत
०१	विद्यापीठाच्या नांदेड-लातूर रोडवरील मुख्य प्रवेशद्वारापासून प्रशासकीय इमारतीकडे येणा-या रस्त्याच्या दोन्ही बाजूने झाडांच्या बुंध्यासभोवती बांधकामामध्ये ओटे तयार करणे	रु. ७३,४६९/-	रु. ७००/-	रु. २००/-
०२	मुख्य प्रशासकीय इमारतीतील टॉयलेट/ बाथरूममध्ये नविन सीपीव्हीसी पाईपलाईन करणे	रु. ६३,२०२/-	रु. ६००/-	रु. २००/-
०३	विद्यापीठाचे मुख्य प्रवेशद्वाराजवळील पोलीस चौकीला रंगकाम करणे	रु. १२,४३७/-	रु. १००/-	रु. २००/-

को-या निविदा कार्यकारी अभियंता, स्वा.रा.ती.म.विद्यापीठ, नांदेड यांचे कार्यालयात दि. ०८/०२/२०१९ ते १४/०२/२०१९ रोजी **दुपारी १२.००** वाजेपर्यंत मुल्य भरून उपलब्ध होतील. निविदाधारकांनी आपले दर सोबत जोडलेल्या विहित **प्रपत्र ब** मध्ये भरून सिलंबद लिफाफ्यात उपरोक्त कालावधीत **दुपारी ३.००** वाजेपर्यंत किंवा त्यापूर्वी मा. कार्यकारी अभियंता यांचे कार्यालयात (हॉल नंबर २०९) सादर करावेत. सादर तारखेनंतर आलेले निविदा विचारात घेतली जाणार नाहीत.

कोणतेही निविदा स्विकारण्याचा / नाकारण्याचा अधिकार विद्यापीठाने राखून ठेवला असून, तो अंतिम राहिल.

स्वाक्ष/-
कार्यकारी अभियंता

टिप :

- १) इसारा रक्कम राष्ट्रीयकृत बँकेच्या धनाकर्षाद्वारे निविदे सोबत जोडावी. धनाकर्ष 'वित्त व लेखाधिकारी, स्वा.रा.ती.म. विद्यापीठ, नांदेड' यांचे नांवाने असावा.
- २) ज्या कंत्राटदारांनी विद्यापीठ संकेतस्थळावरून निविदा पुस्तिका डाउनलोड करून निविदा सादर केल्यास रु. २००/- डी.डी. निविदे सोबत जोडणे आवश्यक आहे.
- ३) सादर कामाचे होणारे देयकापोटी १२ टक्के जीएसटी देय राहिल.

प्रत :

१. कार्यकारी अभियंता, सुचना फलक, प्रस्तुत विद्यापीठ.
२. प्रशासकीय इमारत, सुचना फलक, प्रस्तुत विद्यापीठ.
३. सिस्टम एक्सपर्ट, यूजीसी कक्ष, प्रस्तुत विद्यापीठ, यांना पत्र देवून कळविण्यात येते की, सादर निविदा सूचना विद्यापीठाचे संकेतस्थळावर प्रसिध्दीस द्यावी.

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : विद्यापीठाच्या नांदेड-लातूर रोडवरील मुख्य प्रवेशद्वारापासून प्रशासकीय इमारतीकडे येणा-या रस्त्याच्या दोन्ही बाजूने झाडांच्या बुंध्यासभोवती बांधकामामध्ये ओटे तयार करणे.

Sr.No	Particulars	Unit	Qty.	Rate	Amount
01.	Excavation for foundation in earth soils of types sand gravel and soft murum including removing the excavating of 50 meter etc.	Cum.	4.80	178.00	854.00
02.	Providing and laying cast in situ ready mix cement concrete in M15 of trap granite/quartzite/ gneiss material for plan or molded sills cornice jembs block in (SSR No. 24.14, P.No. 220)	Cum.	0.2	4757.00	951.00
03.	Providing and laying situ ready mix cement concrete M20 of metal for RCC footing etc. (SSR No. 25.11, P.No. 222)	Cum.	1.94	5255.00	10194.00
04.	Providing and laying in situ ready mix concrete M20 of trap/ granite/ quartzite gneiss metal for RCC work in foundation like refl of RCC coloumn etc.	Cum.	0.84	5255.00	4414.00
05.	Providing and laying cast in situ ready mix cement concrete M20 of trap/ granite/ quartzite gneiss for RCC beams and lintels as per detailed design etc. (SSR No. 25.50, P.No. 225)	Cum.	1.10	9010.00	9911.00
06.	Providing and laying cast in situ ready mix cement concrete M20 of trap/ granite/ quartzite gneiss metal for RCC slab and landing as per detailed etc. (SSR No. 25.70, P.No. 227)	Cum.	0.48	10086.00	4841.00
07.	Providing and fixing in position TMT 500 bar rein for cement of various diameters for RCC pile caps, footing foundation slab, beams etc.	MT.	0.4	63994.00	25597.00
08.	Providing sand faced plaster external in cement mortar using approved screened sand in all positions screened including base coat of 15mm thick etc.	Sqm.	23.80	608.00	14470.00
09.	Providing and applying priming coat on concrete masonry asbestos cement plastered surface etc.	Sqm.	23.80	28.00	666.00

10.	Providing and applying two coats external quality of oil paint of approved colour and shade to the plaster surfaces etc.	Sqm.	23.80	66.00	1571.00
Total					73469.00

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent.....% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer

Contractor

Name :

Address:.....

.....

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : मुख्य प्रशासकीय इमारतीतील टॉयलेट/ बाथरूममध्ये नविन सीपीव्हीसी पाईपलाईन करणे

Sr.No	Particulars	Unit	Qty.	Rate	Amount
01.	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. (BD.V 5 Page 551 and as directed by engineer in charge)	Rgm.	6.00	263.00	1578.00
02.	Providing and fixing on walls/ ceiling/ floor 32 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. (BD.V 5 Page 551 and as directed by engineer in charge)	Rgm.	10.00	317.00	3170.00
03.	Providing and fixing on walls /ceiling/ floor 40 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. (BD.V 5 Page 551 and as directed by engineer in charge)	Rgm.	10.00	390.00	3900.00
04.	Providing and fixing on walls/ ceiling/ floor 50 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. (BD.V 5 Page 551 and as directed by engineer in charge)	Rgm.	6.00	564.00	3384.00
05.	Providing and laying in trenches 20 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. (BD.V 5 Page 551 and as directed by engineer in charge)	Rgm.	180.00	222.00	39960.00

06.	Ball valves for 50mm dia. (Sr.No. 282 P.No. 470)	No.	2.00	1290.00	2580.00
07.	Ball cock for 25mm dia. (Sr.No. 278 P.No. 470)	No.	7.00	265.00	1855.00
08.	Tee for 20mm dia. (Sr.No. 265 P.No. 470)	No.	25.00	25.00	625.00
09.	Elbow 90 Degree for 20mm dia. (Sr.No. 259 P.No. 470)	No.	28.00	16.00	448.00
10.	Female adapter (Brass Threads) for 20mm dia. (Sr.No. 296 P.No. 470)	No.	30.00	167.00	5010.00
11.	Female adapter (Brass Threads) for 50mm dia. (Sr.No. 300 P.No. 470)	No.	2.00	1135.00	2270.00
Total					63202.00

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent.....% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer

Contractor

Name :

Address:.....

.....

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : विद्यापीठाचे मुख्य प्रवेशद्वाराजवळील पोलीस चौकीला रंगकाम करणे

Sr.No	Particulars	Unit	Qty.	Rate	Amount
01.	Providing and applying washable oil-bound distemper of approved colour and shade old new surface in two coats including sur folding preparing etc.	Sqm.	62.19	35.40	2201.00
02.	Providing and applying two coats of water proof cement paint of approved manuface and of approved colour etc.	Sqm.	163	57.00	9291.00
03.	Providing and applying two coats of flat oil paint of approved colour to the old structure steel work and iron work previously painted in building including etc.	Sqm.	15.00	63.00	945.00
Total					12437.00

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent.....% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer

Contractor

Name :

Address:.....

.....