॥ सा विद्या या विमुक्तये ॥

स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड

'ज्ञानतीर्थ', विष्णुपुरी, नांदेड – ४३१ ६०६ (महाराष्ट्र राज्य) भारत

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED

'Dnyanteerth', Vishnupuri, Nanded - 431 606 (Maharashtra State) INDIA

Established on 17th September, 1994, Recognized By the UGC U/s 2(f) and 12(B), NAAC Re-accredited with'B++' grade

Fax : (02462) 215572 **ESTATE SECTION** **website:** srtmun.ac.in

Phone: (02462) 215246 **Email:** estate@srtmun.ac.in

Ref: Estate/C.Q.No. 136 -2026/ **Medal** /2026-27/ 314 **Date : 02/11/2026**

Quotation No.136-2026 for Providing and Fixing False Ceiling With Electrical Wiring For Hon. Registrar Cabin at SRTMUN

Our University is interested to Purchase of **Supply of Medal to Student Development** for **Estate/Store /Publication** Dept. SRTMUN. You are requested to send your most competitive rate in Appendix-A subject to below mentioned Objectives, Terms & Conditions in two bid system. (Envelope 'A' and Envelope 'B')

The Quotation in sealed envelope should be submit on or before 19 /11 /2026 up to 3.00 pm in Central Quotation/Tender Department (Finance and Accounts Section).

Terms & Conditions:

1) Rate Quoted should be F.O.R. at Store Section. (Name of Dept.)
2) The Rate quote in given format. (Appendix 'A')
3) Payment will be made after satisfactory delivery & installation as per Purchase order.
4) The Validity period for the rates will be 180 days from the date of opening of the quotations.
5) The University reserves the right to accept any quotation or reject any / all quotations and to order any of the items in any quantity without assigning any reason.
6) Supplier should submit their quotation as per nature of work mentioned in Shop Act unless quotation will not be considered.

A) **Technical envelope (No.1) contains following documents**

1) Index
2) Latest shop Acts Acts/Company Acts,
3) GST No Certificate along with Current GST return copy,
4) PAN Card
5) Aadhar Card (PAN card link with Aadhar Card will be must)
6) Authorization letter from principle company/manufacturer/ Distributor. (If Applicable)

B) **financial envelope contains only price in Appendix- 'A'**

1) Delivery period within 15 days from purchase order.

Sd/-

Finance & Accounts Officer

Index (Attach with document in Involape No.01)

Sr.No	Particular	Number	Page No.
01	Shop Act		
02	GST Registration		
03	GST Return Copy		
04	PAN Card		
05	Aadhar Card		
06	Other If Any		

Bidder Signature and Stamp

Copy to:

1) Senior Programmer, SRTM University, Nanded, Please Publish the said quotation on our university website.
2) Notice Board, Administrative Building/Estate Deptt., SRTM University, Nanded.

॥ सा विद्या या विमुक्तये ॥

स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड

'ज्ञानतीर्थ', विष्णुपुरी, नांदेड – ४३१ ६०६ (महाराष्ट्र राज्य) भारत

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED

'Dnyanteerth', Vishnupuri, Nanded - 431 606 (Maharashtra State) INDIA

Established on 17th September, 1994, Recognized By the UGC U/s 2(f) and 12(B), NAAC Re-accredited with'B++' grade

Fax : (02462) 215572
Phone: (02462) 215246

Engineering Section (Civil)

website: srtmun.ac.in
mail:ee@srtmun.ac.in

दिनांक : /१०/२०२६

निविदा सूचना

कुलसचिव, स्वामी रामांनद तीर्थ मराठवाडा विद्यापीठ, नांदेड हे खालील कामाचे सिलंबद निविदा मागवित आहेत.

अक्र.	कामाचे नांव	कामाची अंदाजित किंमत	इसारा रक्कम	को–या निविदाची किंमत
01	Providing and Fixing False Ceiling with Electrical Wiring for Hon. Registrar Cabin at S.R.T.M.U, Nanded.	रू. २,२४,९८१/–	रू. २५००/–	रू. ५००/–

को–या निविदा/दरपत्रक मा. वित्त व लेखाधिकारी, मध्यवर्ती निविदा विभाग, स्वा.रा.ती.म.विद्यापीठ, नांदेड यांचे कार्यालयात दि. / /२०२६ ते / /२०२६ रोजी **दुपारी १२.०० वाजेपर्यत** मुल्य भरून उपलब्ध होतील. निविदाधारकांनी आपले दर हे विहित **प्रपत्र ब** मध्ये भरून सिलबंद लिफाफ्यात उपरोक्त कालावधीत **दुपारी ३.०० वाजेपर्यत** किंवा त्यापूर्वी मा. वित्त व लेखाधिकारी यांचे कक्षेतील बंद निविदा पेटीत जमा करावेत. सदर तारखेनंतर आलेले निविदा विचारात घेतली जाणार नाहीत.

कोणतेही निविदा स्विकारण्याचा / नाकारण्याचा अधिकार विद्यापीठाने राखून ठेवला असून, तो अंतिम राहील.

कार्यकारी अभियंता

टिप :

१) वित्तीय व तांत्रीक लिफाफा हा स्वतंत्ररित्या द्यावा.

२) सदर कामाचे होणारे देयकापोटी १८ टक्के जीएसटी देय राहील.

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : Providing and Fixing False Ceiling with Electrical Wiring for Hon. Registrar Cabin at S.R.T.M.U, Nanded.

(SSR- 2022-23)

Sr. N0.	Item No	Description	Unit	Qty.	Rate	Amount
1		Providing and fixing false ceiling with eco-friendly light-weight calcium silicate tiles of spintone surface texture aerolite make or equivalent of size 595mm x 595mm having 15mm thick densified micro look edge and 100% humidity resistance incombustible as per BS 46part IV and thermal conductivity 0.043 w/m 0 KC and NRC 0.50 placed in true horizontal level suspended grid of size 600x600mm made from hot dipped G.I. steel sections ion silhouette profile, rotary stitched double webbed white with 6mm reveal profile (white/black), wherein, main T runner of size 42mmx14mm between main tee 600mm center-tocenter and secondary cross T of size 33x14x0.43mm thick of length 600mm long spaced inter-locked at middle of the first crossed T in each panel to form grid of 1200mmx600mm resting on periphery wall Profile wall section 19mm (7+7) x 19mmx0.40thicknesses and laying false ceiling for services like diffusers grills including cutting, making opening for light fittings, fixtures, , smoke detectors etc., wherever required. Main T runners suspended from ceiling with using G.I. soffit cleats of size 25x35x1.6 mm of required length fixed to the ceiling with 6mm dia and 50mm long dash fastener, 4mm dia G.I. adjustable rods with powder- coated/good quality G.I. level adjustment clips of 35x35x0.8mm spaced @1200, center-to- center along main T all complete at all heights as per the specifications, drawings and as per (Sr. No 38.40 page No. 295)	Sqm	80	2045	163600.00
2	1.3.3	Supplying & erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places. as per specification no. WG-MA/BW	Mtr	190	103.95	19750.50
3	1.6.2	Supplying and erecting modular type switch 16A on provided plate and box with wiring connections complete.	Nos	4	113.4	453.60
4	1.6.11	Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring connections complete.	Nos	4	195.3	781.20
5	1.6.27	Supplying and erecting PVC Surface modular switch box with double mounting plate for 2 module complete.	Nos	5	150.15	750.75

6	1.6.32	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 module complete	Nos	1	410.55	410.55
7	1.7.5	Point wiring for light/bell concealed type in min 20 mm HMS PVC conduit with 1.5 sq.mm. (2+1E) FRLSH grade copper wires, modular type switch, earthing and required accessories as per specification no. WG-PW/CW	Nos	12	820.05	9840.60
8	1.7.6	Point wiring for ceiling fan concealed type in min 20 mm HMS PVC conduit with 1.5 sq.mm. (2+1E) FRLSH grade copper wires, modular type switch, earthing and required accessories as per specification no. WG-PW/CW	Nos	4	910.35	3641.40
9	2.1.8	Supplying and erecting LED Panel Light (600mm X 600mm) Max. 35 W having CRCA powder coated housing, polystyrene diffuser having system lumens output of Min 4200 Lumens, min. efficacy of 120 lumen/W, CRI>80, CCT upto 6500K, Beam Angle of 120 deg., max. ripple of 5%, THD<10%, p.f. >0.95, operating range of 120-270V, surge protection of 2.5 kV, Life class of 50,000 Hrs at L70B50 including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete with minimum 2 years warranty as per specification No. FG-IDF/LED.	Nos	8	3031.35	24250.80
10	2.2.3	Supplying and erecting ding dong / electronic musical type call bell with heavy duty coil suitable to operate on 230V A.C. supply erected on polished double wooden block / sunmica block of suitable size.	Nos	2	168	336.00
11	2.2.5	Supplying and erecting electronic type cordless call bell erected on T.W. board having portable bell push working on 9V D.C. battery and (effective range upto 45 meter) bell on 250 V A.C. supply.	Nos	2	582.75	1165.50
					TOTAL RS:	**2,24,981/-**

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent……..% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer **Contractor**

Name: ……..…….....

Address:……..……..……..

……..……..……