॥ सा विद्या या विमुक्तये ॥

स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड

'ज्ञानतीर्थ', विष्णुपुरी, नांदेड – ४३१ ६०६ (महाराष्ट्र राज्य) भारत

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED

'Dnyanteerth', Vishnupuri, Nanded - 431 606 (Maharashtra State) INDIA

Established on 17th September, 1994, Recognized By the UGC U/s 2(f) and 12(B), NAAC Re-accredited with'B++' grade

Fax : (02462) 215572 **ESTATE SECTION** **website:** srtmun.ac.in

Phone: (02462) 215246 **Email:** estate@srtmun.ac.in

Ref: Estate/C.Q.No.145-2026/ **Repair** /2026-27/340 **Date : 25/11/2026**

Quotation No.145-2026 for Minor Repair Works to Two Water Tanks School of Life Science Engineering Dept.at SRTMUN

Our University is interested to Purchase of **Minor Repair Works to Two Water Tanks** for Engineering Dept. SRTMUN. You are requested to send your most competitive rate in **SCHEDULE "B"** Subject to below mentioned Objectives, Terms & Conditions in two bid system. (Envelope 'A' and Envelope 'B')

The Quotation in sealed envelope should be submit on or before 02/12/2026 up to 3.00 PM in Central Quotation/Tender Department (Finance and Accounts Section).

Terms & Conditions:

1) Rate Quoted should be F.O.R. at (as per mention Tender/Quotation.)
2) The Rate quote in given format. (**SCHEDULE "B"**)
3) Payment will be made after satisfactory delivery / installation work Completion as per Purchase order.
4) The Validity period for the rates will be 180 days.
5) The University reserves the right to accept any quotation or reject any / all quotations and to order any of the items in any quantity without assigning any reason.

A) **Technical envelope (No.1) contains following documents**
   1) Index
   2) PWD Registration/Contractor Registration/Shop Acts
   3) GST No Certificate along with Current GST return copy,
   4) PAN Card
   5) Aadhar Card (PAN card link with Aadhar Card will be must)
   6) Authorization letter from principle company/manufacturer/ Distributor. (If Applicable)

B) financial envelope contains only price in **SCHEDULE "B"**

C) Work Completion as per Work order.

Sd-

Finance & Accounts Officer

Index (Attach with document in Involape No.01)

Sr.No	Particular	Number	Page No.
01	PWS Reg.		
02	GST Registration		
03	GST Return Copy		
04	PAN Card		
05	Aadhar Card		
06	Other If Any		
07	Mobile No		

Bidder Signature and Stamp

Copy to:

1) Senior Programmer, SRTM University, Nanded, Please Publish the said quotation on our university website.
2) Notice Board, Administrative Building/Estate Deptt., SRTM University, Nanded

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : जैवशास्त्र संकुल इमारतीच्या समोरील पाण्याच्या दोन हौदाची किरकोळ दुरूस्ती करणे.

(SSR- 2023-24)

Sr.No.	Particulars	Unit	Qty.	Rate	Amount
1	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. (Item No. 21.38)	Cum.	16.84	1382/-	23273/-
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete(Item No. 24.01)	Cum.	2.90	5830/-	16907/-
3	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete.(Item No. 27.05)	Cum.	1.20	7994/-	9593/-
4	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand .... etc. complete (Item No. 32.11)	Sqm.	8.50	639/-	5431/-
5	Providing fine cement finish 1.5 mm thick over green plaster surface including scaffolding curing etc. complete. (Item No. 32.21)	Sqm.	32.36	72/-	2330/-
6	Removing mud plaster including disposing of the spoils as directed with all leads, lifts etc. complete (Item No. 46.23)	Sqm.	35.52	15/-	533/-
7	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts (Item No. 46.09)	Cum.	8.16	335/-	2734/-
8	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. (Item No. 33.41)	Sqm.	18.96	1252/-	23738/-
	Total				84,539/-

Page No. 2...

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent……..% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer

Contractor

Name: ……..…….....

Address:……..……..……..

……..……..……