॥ सा विद्या या विमुक्तये ॥

स्वामी रामानंद तीर्थ मराठवाडा विद्यापीठ, नांदेड

'ज्ञानतीर्थ', विष्णुपुरी, नांदेड – ४३१ ६०६ (महाराष्ट्र राज्य) भारत

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED

'Dnyanteerth', Vishnupuri, Nanded - 431 606 (Maharashtra State) INDIA

Established on 17th September, 1994, Recognized By the UGC U/s 2(f) and 12(B), NAAC Re-accredited with'B++' grade

Fax : (02462) 215572 **ESTATE SECTION** **website:** srtmun.ac.in

Phone: (02462) 215246 **Email:** estate@srtmun.ac.in

Ref: Estate/C.Q.No.146-2026/ **Repair** /2026-27/341 **Date : 25 /11/2026**

Quotation No.146-2026 for Providing Laboratory Plat form and Other Miscellaneous Works School of Life Science Engineering Dept.at SRTMUN

Our University is interested to Purchase of **Laboratory Plat form and Other** for Engineering Dept. SRTMUN. You are requested to send your most competitive rate in **SCHEDULE "B"** Subject to below mentioned Objectives, Terms & Conditions in two bid system. (Envelope 'A' and Envelope 'B')

The Quotation in sealed envelope should be submit on or before 02/12/2026 up to 3.00 PM in Central Quotation/Tender Department (Finance and Accounts Section).

Terms & Conditions:

1) Rate Quoted should be F.O.R. at (as per mention Tender/Quotation.)
2) The Rate quote in given format. (**SCHEDULE "B"**)
3) Payment will be made after satisfactory delivery / installation work Completion as per Purchase order.
4) The Validity period for the rates will be 180 days.
5) The University reserves the right to accept any quotation or reject any / all quotations and to order any of the items in any quantity without assigning any reason.

A) **Technical envelope (No.1) contains following documents**
   1) Index
   2) PWD Registration/Contractor Registration/Shop Acts
   3) GST No Certificate along with Current GST return copy,
   4) PAN Card
   5) Aadhar Card (PAN card link with Aadhar Card will be must)
   6) Authorization letter from principle company/manufacturer/ Distributor. (If Applicable)

B) financial envelope contains only price in **SCHEDULE "B"**

C) Work Completion as per Work order.

Sd/-

Finance & Accounts Officer

Index (Attach with document in Involape No.01)

Sr.No	Particular	Number	Page No.
01	PWS Reg.		
02	GST Registration		
03	GST Return Copy		
04	PAN Card		
05	Aadhar Card		
06	Other If Any		
07	Mobile No		

Bidder Signature and Stamp

Copy to:

1) Senior Programmer, SRTM University, Nanded, Please Publish the said quotation on our university website.
2) Notice Board, Administrative Building/Estate Deptt., SRTM University, Nanded

SWAMI RAMANAND TEERTH MARATHWADA UNIVERSITY, NANDED.

ENGINEERING DEPARTMENT

SCHEDULE "B"

Name of work : जैवशास्त्र संकुलातर्गत ए–विंग इमारतीच्या प्रयोगशाळेकरीता ओटा व इतर किरकोळ कामे करणे.

(SSR- 2022-23)

Sr.No.	Particulars	Unit	Qty.	Rate	Amount
1	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion etc. complete. (Item No. 32.12)	Sqm.	19.80	563/-	11147/-
2	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for foundation / steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven etc. complete. (Item No. 24.04)	Cum.	1.98	6359/-	12591/-
3	Providing 25 mm to 30 mm thick partition of polished black kadappa stone slab of approved quality including giving required size and shape etc. Fixing in cement mortar 1:3 curing and cement etc. complete. a) One side polish etc. complete. (Item No. 33.32)	Sqm.	10.80	988/-	10670/-
4	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black granite / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with full moulding the edges etc. complete . Both side polish (Item No. 33.36)	Sqm.	8.74	4019/-	35126/-
5	Providing and fixing white glazed earthenware sink 600mm x 200mm x 450mm including all connection of the G.I. supply and P.V.C. waste pipes up to the outside face of the wall, cold water chromium plated screw down bib tap, rolled steel or C.I. brackets, rubber plug with chain and stop tap complete. (Item No. 41.75) (Fitting labour charges)	No.	02	1834/-	3668/-
6	Dismantling brick masonry in Mud and stacking the materials as directed with all leads, etc, complete. (Item No. 46.08)	Cum.	0.108	260/-	28/-
7	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete (Item No. 46.19)	Sqm.	1.08	45/-	49/-
8	Removing mud plaster including disposing of the spoils as directed with all leads, lifts etc. complete.(Item No. 46.23)	Sqm.	1.08	15/-	16/-
				Total	**73295/-**

Page No. 2...

I do hereby tender to execute the above mention description of work in accordance with condition noted below in consideration of payment being made for the quantity of work executed at percent……..% below/above, the amount worked out at the rates entered in memorandum of rates schedule 'B' hereto

Executive Engineer

Contractor

Name: ……..…….....

Address:……..……..……..

……..……..……